



### Construction and Finish

1. The Essential Series Planters are 3 inch thick cast concrete that are manufactured with standard 1", 1.5", 2" drain holes or no drain holes. They have an average strength tested at 28-30 days of 5,810 psi.
2. Planters are lightly sanded and sealed, inside and outside, to enhance color and protect surfaces from moisture, dirt, and stains.

### Transport and Installation

1. Due to size and weight of planters, great care should be taken in moving, transporting, and installation.
2. Planters should be kept in an upright position and are best transported using wood pallets with pallet trucks or a forklift for greater distances.
3. Extreme care should be taken to protect planter bases, edges and rims from chipping with use of protective cushioning or moving blankets.

### Cleaning and Maintenance

1. Planters should be cleaned on a biannual or annual basis. Use warm, mild soap and water with soft cloth. Do not use wire brushes or high-pressure washers.

### Size and Capacity - Precast

	l x w x h	capacity	Precast avg weight
ES_40	26"x26"x40"	53 gal/7.09 ft <sup>3</sup>	900 lbs
ES_30	30"x30"x30"	44 gal/5.88 ft <sup>3</sup>	880 lbs
ES_24	48"x24"x24"	60 gal/8.02 ft <sup>3</sup>	887 lbs
ES_18	30"x30"x18"	38 gal/5.08 ft <sup>3</sup>	525 lbs
ES_14	42"x42"x14"	52 gal/6.95 ft <sup>3</sup>	725 lbs
ES_14.2	26"x26"x14"	16 gal/2.14 ft <sup>3</sup>	385 lbs



Form and Fiber Inc. All rights reserved. © 2017.  
Made in the USA.