



Construction and Finish

- The Box Series Planters are available in a ASTM A606 Type 4 Cor-Ten® Steel option. Planters are offered in two finish options:
 - Un-weathered; no exterior sealant
 - Pre-weathered with exterior sealant
- Thicknesses can range from 10 GA, 3/16", 1/4", 3/8" up to 1/2" thick, based on designer specification, and/or manufacturer recommendation for size and length of run.
- Oversized boxes are constructed with internal reinforcement comprised of horizontal stiffeners, and vertical gussets. Specific dimensions for spacing of internal reinforcement is submitted via shop drawing for approval, prior to construction.
- Planters are sealed internally with a waterproof sealant along all seams and welded areas only, and are manufactured with standard 1", 1.5", 2" drain holes or no drain holes.
- Planters do not weather with consistent color and patina among groups. Units weather at varying rates and develop coloration which is unique to each individual unit. (Standard level of finish shown)
- Standard sealant is a light metal sealant with matte finish applied to exterior and is a temporary sealant for handling. Units will continue to oxidize, patina will darken and sealant will wear off. Purchasers should exercise caution in placement as units may leach onto adjacent surfaces until fully weathered and self sealed.



Customization

- Unit price based on designer specified dimensions and US Steel prices; Contact Form and Fiber for individual pricing for your project.
- Pricing may vary, based on steel thickness and reinforcement requirements.
- Optional bottomless box frames for longer installations.